



**Tree planting schedule**

periphery & boundaries away from the courtyard  
 Stock size 20-25cm wire rootballed with platypus No2 underground guys, 1000 X 1000 X 900 pits with perforated 50mm wavincoil and graded bark flakes finish  
 Stock schedule, widely available:  
 2no *Acer campestre* wire rb 20-25cm clearstem  
 3no *Acer griseum* wire rb 20-25cm clearstem  
 2no *Betula jacquemonti* wire rb 20-25cm multistemmed  
 2no *Betula pendula* wire rb 20-25cm clearstem  
 2no *Robinia pseudoacacia* wire rb 20-25cm clearstem  
 2no *Pyrus calleryana* Chanticleer wire rb 20-25cm clearstem

Protect and retain existing large maple tree  
 17m section of boundary trees and shrubs protected and retained, trimmed back to 2m or so  
 Fit furniture to residents' socialising area, surfacing, seating, pergola

Existing NW corner jungle encroachment beneath maple tree shown enclosed by red dotted line. Cut back to fence line and made good to lawn

electricity substation and single garage unit

Trees to be removed and made good, root-ground shown in red, most boundary trees & around garages

Existing buildings, 4 blocks of garages, to be removed shown in red dashes

Replace existing boundary fencing with 1.8m and 2.0m timber close-board and 3 rail on concrete posts, cladding 20mm treated softwood clad in situ, north, south, east and west boundaries



Underground services survey information complete for the rear area and the eastern side of the frontage, absent from the west side of frontage

Protect and retain existing pair of trees *Betula pendula* and *Robinia pseudoacacia*.  
 Hedge planting to mix B front boundary behind dwarf wall

Temporary tree watering point. 2 lines connect here for bowser

Utilities to connect new block to mains services to be located in access road